



Fact Sheet

Togus VA Medical Center Force Main and Pump Station Connection to the Greater Augusta Utility District

The proposed project is to abandon and decommission the existing Togus VA Medical Center on-site wastewater treatment facility and discharge to Togus Stream. Togus VA wastewater will be pumped to the Greater Augusta Utility District's treatment system. The connecting point to the Greater Augusta Utility District's collection system will be on Eastern Avenue. Project specifics include:

- 1) closure of the existing wastewater facilities at Togus VA;
- 2) modifications to the pumping facilities at Togus VA Medical Center;
- 3) construction of approximately 23,200-feet (4.4-miles) of new 10-inch wastewater force main from Togus VA Medical Center along Eastern Avenue (Route 17) to the gravity main terminus at the intersection of Kennison Street;
- 4) construction of approximately 2,300-feet of new wastewater gravity main along Eastern Avenue between Kennison Street and Arsenal Street;
- 5) construction of approximately 1,800-feet of new gravity storm drain along Eastern Avenue and Arsenal Street between Hospital Street and Kennebec River;
- 6) construction of approximately 1,300 linear feet new water main along Eastern Avenue between Hospital Street and Arsenal Street;
- 7) road reconstruction of Eastern Avenue between Hospital Street and Arsenal Street; and
- 8) new bituminous sidewalk along Eastern Avenue between Arsenal Street and Cony Road.

Project is being funded by the Veterans Administration and financed through the State Revolving Loan Fund Program.

Owner:	Greater Augusta Utility District, Augusta, Maine
Engineer:	Woodard & Curran, Portland, Maine
Contractor:	D&C Construction Co., Inc., Waterboro, Maine

Project Cost
Construction Bid: \$5.5 million
Total Project Cost: \$6.9 million

Construction Project Schedule
Start: October 2008
Completion: November 2009